

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report 18 When handed in at Local Office 18 Port of London
No. in Reg. Book 228 Survey held at London Date, First Survey June 15 Last Survey July 2 1898
(No. of Visits) Master

TONNAGE: Built at St. Yarmouth By whom Fellow Harb When 1892 11
GROSS 94 Owners Walker Howard & Co Port belonging to London
UNDER DE 92
NET 84 Owners' Address

Surveyed Afloat or in Dry Dock? Under Name of Dock Limehouse Destined Voyage
WB=CelUDBoRDBa feet; uE&B feet; J feet; }
total capacity tons. FPT tons; APT tons; MT feet tons. }

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).
CHARACTER: * for Special Survey. Date of last Survey and of Periodical Surveys. Years assigned no. or expired. Machinery and Boiler Surveys (including date of N.B., if any).
+ 10 A 1
11.92
G. I. B.

Society's Freeboard (if assigned) as painted on Ship and now verified } ft. ins.
Last Report, No. 2413 Port

REPAIRS, OR EXAMINATION AS PER RULE, FOR Half Time

This vessel has now been placed on the griddiron, the hold & peaks cleared, and listings out out at each end as required. Aircrunes & timbers opened out; windlass unhooked & sufficiently stripped for manimation, topsides scraped bright in places as required, Chain cables raved, & equipment manimed. Iron bolts & treenails, in pieces of equipments, backed out for manimation. Iron done. The treenails & bolts driven out for manimation was renewed, the deck recaulked, bolts & seams inside recaulked where required; main-booms renewed & rigging overhauled. Pumps tested & found good.

SUMMARY OF DAMAGE REPAIRS:—

	Plates.	Frames.	R. Frames.	Floors.	Beams.	Str. Plates.	Dk. Plates.	Other Items:—
Renewed								
Removed and Faired or Repaired								
Faired or Repaired in place								

PRESENT CONDITION OF THE

Decks	good	Stringers	—	Engine Room Skylights	—	Boats	good	
Caulking of Decks	—	Inner Bottom Plating	—	Coal Bunkers, Open'gs, Lids, &c.	—	Masts, Yards, &c.	—	
Waterways	—	State of Tanks now tested	—	Scuppers	—	Condition, how ascertained	manimed	
Coamings	—	Bulkheads	—	Cargo Hatchways	good	(State if wedges removed)		
Beams & Fastenings	—	Ceiling	—	Hatches	—	Sails	good	
Outside Plating	—	Cement or Asphalt (State which.)	—	Planking of Wood Vessels	—	Equipment letter	—	
Caulking of ditto	—	Rudder	good	Treenails ditto	—	Anchors, No. of	2 B 15 1 K	
Rivets	—	Windlass	—	Breasthooks & Stemson ditto	—	Cables (State if now ranged)	yes	
Breasthooks & Crutches	good	Have Pumps now been examined and found efficient?	yes	Transoms, Pointers, & Crutches ditto	—	" length (on board)	120 size 7/8	
Transoms	—	Have Sluice Valves now been examined and found efficient?	—	Timbers of Frame at openings ditto	—	" Eule length (per Table 22)	120 size 3/4	
Frames	—	Have Watertight Doors now been examined and found efficient?	—	Ditto ditto at other places ditto	—	Hawsers & Warps	good	
Reverse Frames	—	Dblng. Plates under Sounding Pipes	—	Stringers, Clamps & Shelves ditto	—	Standing & Running Rigging	—	
Floors	—			Salting (State if examined.)	—			
Keelsons	—			Copper, or Y.M. (State if on Felt.)	—			
				When put on, Month Year	—			

General Observations, Opinion as to Class, Recommendation, &c.:—
State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 1,98," or "to remain as classed and to have record of survey, 1,98, and the notations of ss No. 1-98 and ptND98, &c."

This vessel is in good condition than carried out the requirements for this survey it is eligible in my opinion to remain as classed with record of H.T. Lon 98, & date of last survey 27.98

Office Fee (if chargeable) per Scale II., Sec. 27 £ : :
Survey Fee (per Section 28) £ : :
Special Damage or Repair Fee (if any) (per Sec. 28.) £ 2 : 3 : 0
Travelling Expenses (if chargeable) £ : :
Second Surveyor's Fee (if any) £ 2 : 17 : 0
Fees applied for, 7/7 98
Received by me, [Signature]
Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute
Character assigned 10 A 1 26.9.98
FRI 8 JUL 1898
Lloyd's Register Foundation
LON716-0033