

Dear Sirs.

29<sup>th</sup> April. 1870  
Yours

28<sup>th</sup> inch

Barin

is made by Barin

J. S. Robertson etc

105

The hull plates of the steam space to make  $\frac{1}{2}$  inch thick; other two stay tubes to fitted in the top row; the butt straps of the shell to make  $\frac{1}{2}$  inch thick; the second stays in the top row and at sides of the side water space have each an effective area of 8.6 square inches all the other second stays have each an effective area of 8.33 square inches; all the construction chamber plating to make  $\frac{1}{2}$  inch thick; the furnace plating to make  $\frac{1}{2}$  inch thick; the shell to be tested as required by the Rules; & the usual conditions of survey relating to completed work.

I enclose the drawing, which please return when noted, for the Surveyor's signature.  
I am Dear Sirs.

Yours truly & respect

Yours faithfully.

Approved by Rev.

Secretary



© 2021

Lloyd's Register  
Foundation

LON 725-0005