

Dear Sir,

1<sup>st</sup>, Jan<sup>y</sup>, 1894  
your

no today's date  
donkey  
sellers  
Castle & Nathan Castle

your  
the steamer "Dunker"

80

the longitudinal stay marked x at  
the middle line of the boiler at top  
of frames be dispensed with, or  
if fitted, a clear space of 3 inches  
between it & the combustion chamber  
sides be left; the vertical stays of the  
steam dome be screwed into the boiler  
& dome covers, or internal nuts be  
fitted; the tensile strength of the  
steel be from 26 to 30 tons per square  
inch, & the steel be tested by the  
Society's surveyors as required by the  
Rules; the boilers in other respects  
be built in accordance with the  
plan, under the usual conditions of  
survey & testing, & the entire satis-  
faction of the Society's local Engineer  
surveyors.



© 2021

Lloyd's Register  
Foundation

LON728-0028 1/2



The above report is  
entirely correct which should be  
noted by those who read,  
for the purpose of the  
committee.

Very truly  
yours,  
J. H. [unclear]

[unclear]

[unclear]  
[unclear]  
[unclear]  
[unclear]



© 2021

Lloyd's Register  
Foundation

LON728-0028 1/2