

Dear Sir,
 and inst.
 donkey
 works
 Feab
 you
 at your
 the cleaner

80

the crown stays be fitted 18 inches from the centre one, instead of 20 inches as proposed; the diameter of the stiffening ring on top plate of boiler be reduced to 4 feet outside diameter and 2.6 inside diameter, the connections of the crown stays to the fire box crown be equal in strength to the body of the stays, the steel used be tested as required by the Rules, and the boiler be built under the usual conditions of survey and testing, and to the entire satisfaction of the Society's Engineer Surveyor.

The plan sent is returned herewith, & I have to ask you to kindly forward it again, when noted, for the



© 2021

Lloyd's Register
Foundation

LON 728-0264 1/2

superior guidance during construction.
I also enclose a special
return order form, which please to
send enough to sign and return to me
at your convenience.

I am,

Dear Sir,

Yours faithfully

R. W. D. [Signature]
Secretary.

John T. [Signature]
Supt.
Gen'l Steam Pwr. Co's Bldg.
Westford,
P.E.



© 2021

Lloyd's Register
Foundation

LON 728-0264 1/2