

22<sup>d</sup> December  
1896.

Dear Sir,

I am in receipt of  
your letter having reference  
to the riveting of the longitudi-  
nal seam of the shell of  
the boiler now building by  
you, and in reply beg to  
state that there will be  
no objection to the pitch  
of the rivets being  $4\frac{5}{8}$ "  
diam holes  $\frac{1}{8}$ " as this gives  
percentages of 77.2 & 91.0  
which with  $\frac{3}{8}$ " plates and 90°  
diam boiler gives 126.9 lbs

per sq inch working

In working out the  
percentage of the rivets, I  
would respectfully point out  
that it is the diameter of  
the rivet holes that

I am

Yours

A. Holliman Esq.

King's College



© 2021

Lloyd's Register  
Foundation

LOW31-008