

Telegraphic Address.
"COMMITTEE, LONDON."

Any further communication on this
subject should be addressed to
THE SECRETARY,
and the following Initials should be
quoted in the left hand corner.

Lloyd's Register of British
and Foreign Shipping.
2, White Lion Court, Cornhill, E.C.

"Agnes." 8/s.

This steamer was built in 1870. Now nearly
29 yrs old. The Special Survey No 3 (second series)
due in January 1899 & should be completed
before January 1900.

The examination & repairs to the
Floors &c in the Engine & Boiler space, ^{in May 1897} might be
regarded as part of the Special Survey No 3.
& the close ceiling not removed from the Bunkers
provided that the bunkers were cleared
& a strake of ceiling lifted. & the dirt & matter
removed from the lumbers in this compartment
for examination of floors. Cement &c & The
plating drilled, the close ceiling removed
& plating under side lights examined. the
oxidation beaten off the surfaces of the iron
work, tanks opened up & tested. decks examined
also ^{masts} spars, rigging. pumps. Sluice valves called ranged
& the SS No 3 (second series) otherwise fully complied with

LONT31-0113

S. D. T. 1/2/98.