

S.S. "Altata" & S.S. "Mayatlan"

The Surveyor should be informed that the requirements for the special survey of the machinery are as follows.

The vessels should be placed on the Slipway. The screw shafts, drawn in, and examined. The propellers, stern bushes, sea-connections, Cylinders, pistons, slide valves, pumps, condensers, crank shafts, thrust shafts & tunnel shafts examined.

The main & donkey boilers should be opened & the various parts, together with the safety-valves, examined, & if found in good condition.

The safety valves to be adjusted under steam to the pressures given in the Register Book

S.S. "Altata" main boiler pressure 75 lbs. Donkey boiler pressure 75 lbs.
S.S. "Mayatlan" main boiler pressure 160 lbs. Donkey boiler pressure 80 lbs.

In the event of the boilers being found defective in any way the defects must be taken into consideration & the safety valves adjusted to a safe working pressure

J. S.

1.9.96



© 2021

Lloyd's Register
Foundation

LON731-0349