

Extract from Mr. Martins Report, dated August 1846

Names of the Red Pine Planks in Bottom are wrought with their heart sides outwards which is wrong in principle, they are much split and shatter, with Cuppy Shakes, very difficult to Caulk; two of them decidedly unfit from bad shakes, and Pith, and two other Planks of Bottom unfit being also damaged; several other planks of Bottom required their defects cut out for further examination.

Recommended the four defective Planks of Bottom to be replaced and other Planks of Bottom to be prepared for further examination.



© 2021

Lloyd's Register
Foundation