

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

* * * The particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) _____

Official Number.	Name of Ship.	No., Date, and Port of Registry.
110,202	Aurora	² / ₁₈₉₉ Granton

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw	Leith	1899	Ramage & Ferguson Leith

Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	105	2
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	105	
Rigged ...	Ketch	Main breadth to outside of plank ...	20	6
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	10	9
Build ...	blincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		
Galleries ...	—	Depth from top of beam amidships to top of keel ...	12	25
Head ...	—	Depth from top of deck at side amidships to bottom of keel	12	64
Framework and description of vessel ...	Steel	Round of beam ...		4
Number of Bulkheads ...	Three	Length of engine room (if any) ...	19	1
Number of water ballast tanks, and their capacity in tons ...	One - 16 tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ...	292 tons.	Ditto per inch immersion at same depth ...	3.70 tons.
--	-----------	--	------------

PARTICULARS OF ENGINES (if any).

No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
Three	Triple expansion	British	1899	Ramage & Ferguson	Three 12" x 19"	21"	754 350
Number ...	Boilers ... One				4		
Iron or Steel	Steel		1899	Leith	30"		10 1/2 Knots
Pressure when loaded	180 lbs						

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	139.77	On account of space required for propelling power	92.35
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Space or spaces between Decks ...		These spaces are the following, viz. :—	
Poop ...		Lower forecastle forward	11.72
Forecastle ...		Under deck aft	10.36
Round House ...			
Other closed-in spaces, if any, as follows :—			
Breaks 3.82		Deductions under 879 of M. S. A. 1894	
Side House 67	6.49	Cubic Metres. Boatwain's store 3.02	
Spaces for machinery, light, & air, under S. 78(2) of M. S. A. 1894. —	12.32	Master 2.76	5.58
Gross Tonnage ...	158.58		
Deductions, as per Contra ...	120.21		
Registered Tonnage ...	38.37	Total Deductions ...	120.21

Name of Master George Liston

Certificate of Service No. Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Newhaven Trawlers Limited of 13 Frederick St. Edinburgh
Shipowners = sixty-four shares

Dated 5th April 1899