

STEEL YARD SECTIONS

26.3.91.

Nº 261 SHIP

FORE MAIN & MIZEN

LOWER YARDS

Length bleated	79-9"	Dia Thickness
Dia at centre		19 x 7/20
" 1 st Quarter		18 1/2 x 6/20
" 2 nd "		17 1/8 x 6/20
" 3 rd "		14 1/4 x 5/20
" Ends at bleats		9 1/2 x 3/16
<u>Butts lapped & treble rivetted</u>		

FORE MAIN & MIZEN

LOWER TOPSAIL YARDS

Length bleated	75-9"	
Dia at centre		18 6/20
" 1 st Quarter		17 1/2 6/20
" 2 nd "		16 1/4 6/20
" 3 rd "		13 1/2 5/20
" Ends at bleats		9 3/16
<u>Butts lapped & double rivetted</u>		

FORE MAIN & MIZEN


UPPER TOPSAIL YARDS

Length bleated	69-0	
Dia at centre		17 x 6/20
" 1 st Quarter		16 1/2 x 4/20
" 2 nd "		15 1/4 x 6/20
" 3 rd "		12 3/4 5/20
" Ends at bleats		8 1/2 3/16

Butts lapped & double rivetted

Seams of all Yards single rivetted

Yards doubled in way of Shropps & to beyond truss hooks.




© 2021

7th Floor, 2021
SHROOP & CO. LTD.
RESEARCH & DEVELOPMENT
FEMINIST FOUNDATION
23/3/91

Ant. Rk. Widener
 Milford Haven
 Rept. 1814

LRF-PUN-MIL770-0007-P



© 2021
 Lloyd's Register
 Foundation