

© 2018
Lloyd's Register
Foundation

SURVEYOR'S REMARKS.

Timbering.

The Quality,
Squaring, and
Workmanship.

Aground
Good keel 2 lengths. Am. Elm, 10 1/2 sided 9 in. having
lately new. Frame may be considered of mixed oak
some live oak in bottom, top mixed foreign oak. These
in way of keelson sound bare square, Stern, Stern post,
Hooks, H. beams, Beams, & H. beams, Thru bolt heads, House
timbers & coamings are all in fair sound condition.

Planking.

Outside and Inside
Quality, Edging,
and Workmanship.

Deck fair, Waterways nearly new R. pine South Plank
Shear, all outside planks, with water mixed oaks, some
Am. & Am. Elm, bottom planks, oak, all in fair
sound condition, but not regular shifted in butts
having 1. 2. 3. Shakes between. — Clamps & bilge planks
flat of floor, mixed oak the part of ceiling mixed Elm
pine oak in good fair sound condition with a good
proportion of treenails this in ceiling.

Fastenings.

If Sheathed,
Single Doubled, or
Bottom Felled.

Deck & Mold beams fastened by double ledging knees
with good arms. — 5. hooks forward beam end firm
in fastening. I shew no movement. — This vessel
has a rising floor have 2. Bilge Clogs on each 9 in.

Repairs.

Survey'd
aground
Yellow house
house
So. Shields.

General Observations
and Opinion as
required by the
Instructions.

That this vessel, having been kept well up in repairs &
is now in a fair state of equipment, fit to carry cargo,
not in their nature liable to sea damage, & conforming
with the foregoing scale of dimensions is in my opinion
entitled to be classed. **F.**
according to the rules for classification laid down by
the committee.

Certificate granted 1 1 0

The Amount of the Fee, £ 1 : 1 : 0 is received by me.

Committee Minute

14 February 1835

Character assigned

F. 1
M. C. Smith