

now ready by owners

## CERTIFICATE FOR STEEL HAWSER.

We hereby Certify that the 90 fathoms of  
4 inch circumference galvanized Steel Wire Hawser,  
supplied to Messrs Swan & Hunter, Wallsend  
for their Ship No. 53 is composed  
of 72 wires (Number 14 Birmingham Wire Gauge),  
and that the several wires, after being galvanized, have been  
subjected to, and have successfully withstood the following  
tests, viz.:

Each wire has withstood a tensile strain of 10 cwt

It has withstood being twisted 22 times in itself in a length  
of eight inches.

It has been doubled and twisted eight times round itself as a  
core and untwisted again without fracture.

We guarantee that the Steel Wire Hawser of  
4 inches in circumference above described will bear a strain  
of  $32\frac{3}{4}$  tons without breaking.

May 4th 1881

Newcastle-on-Tyne



P. Hood Haggie

Manufacturers



NWIC748 - 0079

No 53 Steel Hawser  
Certificate  
not for terrors.

© 2019  
Lloyd's Register  
Foundation

