

Newcastle-on-Tyne


May 9th 1895

G. Abbott

The owners representatives Mr. Roberts
having the S.S. "Glenavon" of Glasgow while
that vessel was lying in the River Tyne, on the
2nd of May 1895, in order to ascertain the
damage said to have been caused through
collision with the S.S. "Fortunatus" of W. Hartlepool
off Hartlepool Head on the 1st inst. while on
a voyage from London to Middlesbrough
for particulars of which see Log Books.
On examination found the stem to be broken
in two places and recommended vessel to
be placed in dry dock.

On further examination of the vessel in the
dry dock of the Wallend Slipway and
Engineering Co. Newcastle-on-Tyne on the
3rd of May and subsequent dates found
as follows:- On Starboard bow, six plates
broken and damaged and on Port bow,
seven plates and one frame broken and
three frames cracked.

Recommended: Vessel to be unwarmed,



© 2021

Lloyd's Register
Foundation

NW841-0153 1/2

and six plates to be taken off on Starboard
bow and renewed, and on Port bow, seven
plates to be removed and renewed, one frame
and nerve bar to be taken out for a length of
nine feet and renewed and bosom pieces filled
and three frames and nerve bars to be
repaired with long bosom pieces, a breast hook
to be fitted in fore peak in way of damaged
frames and the fore peak keeled with water
to the height of the load water line. The whole
to be completed so as to place the above
mentioned vessel in as good and seaworthy
condition as before the accident.

G. Admire

Fwd £3-3-0
less 10/- 6. 0
£ 2. 17. 0



© 2021

Lloyd's Register
Foundation

NWCS4H+0153 2/2