



REGISTER
MAR 1914

Lloyd's Register of British & Foreign Shipping,

Collingwood Buildings, Newcastle-on-Tyne.

March 21st 1914

5 Enclosures

Sir

I beg to Submit for the Consideration of the Committee, plans shewing position & arrangements of cargo doors proposed to be fitted in the S.S. Ingeli, N^o 223 in the Register book, between the spar & main deck.

It is Submitted that in view of the position of the doors with regard to the ends of the bridge, which the Owners Superintendent States cannot be altered, the Stringer plate should be doubled above the door, extending same into bridge, the top of the opening to be lowered - Say 12 - & shell doubling increased at this part, and a shelf plate fitted to carry beams in way of door, & the amendments as indicated in plan on the plans be adopted, the proposal in

NWC876-0077 1/2

my opinion will merit the favorable
Consideration of the Committee
It has been pointed out to the Repairers
that entirely new plans should have
been provided (not amended similar plans
as used in this instance), but they
state that the urgency of the case
prevented new plans being prepared
in the time available

The approximate position of load line
is shown on plan in pencil
The approved Midskip Section & Profile is
forwarded herewith for reference.

The Secretary
London

I am Sir
Your obedient servant
John F. Sherwood



© 2021

Lloyd's Register
Foundation

0077 3/2

Referred to the Chief Ship Surveyer.

Wmo

MAR 23 1914



© 2021

Lloyd's Register
Foundation