

**REPORT of SURVEY for REPAIRS.**

No. 12429 Survey held at Liverpool Date 30 Jan<sup>y</sup> 1854  
 on the Ship Eveline Master Thomas Patterson  
 Tonnage 898 894 Built at Quebec When built 1853  
 By whom built 3500 J. Lemelin Owners Hammond & Co  
 Port belonging to London Destined Voyage not fixed  
 If Surveyed Afloat or in Dry Dock in Dry Dock & Afloat

Last Survey, No. 79 Port St. Lawrence Classed

REPAIRS At present time has had put to deck beams 27 pairs of iron hanging knees, and to hold beams 26 pairs of iron hanging knees, extending down to take two bolts to the substantiated part of the floors, except forward and aft when obstructed by the Pointers and Masthooks. To 2 Deck Beams iron hanging knees cannot be properly put. The bottom has been sculked and sheathed with Yellow Metal or felt; And the following articles which were not supplied at Quebec have now been put on board. Say 120 fathoms of 1 3/4 Chain. 75 fathoms of 1<sup>st</sup> Chain. Anchor 35-2-y steam Anchor 12-0-12, Midge, 90 fathoms 11 Hawser 1 @ 6", one for sail, one for Topmast stay sail, and one Toprail.

## Present Condition of the

Decks	Good	Treenails	appear	Good	Windlass and Capstan	Good
Waterways	D.	Breasthooks and Stemson		Good	Pumps	D.
Comings	D.	Transoms, Pointers, and Crutches		D.	Boats	D.
Upper Deck Beams & Fastenings	D.	Timbers of the Frame	appear	Good	Masts, Yards, &c.	D.
Lower Deck Beams & Fastenings	D.	Keelsons		Good	Sails	well found
Planksheers	D.	Clamps and Shelves		D.	Anchors	No. of 3 Bowers, Stem & Midge
Sheerstrakes	D.	Ceiling		D.	Cables	well found
Topsides	D.	Rudder		D.	Hawsers and Warps	well found
Wales	D.	Copper	yellow Metal	When put on present time	Standing & Running Rigging	Good
Plank (Bottom) and Counter	D.					

## General Observations and Opinion,

Is in an efficient state, fit for the conveyance of dry and perishable cargoes with safety, to and from all parts of the world and in my opinion should be classed to A1, as recommended by Mr Mungie at Quebec.

The Amount of Fee.....£ 1 : - : - is received by me,

Feb

Special..... 3 : 3 :

Certificate (if required) Gratis

Committee's Minute

Character assigned

3<sup>rd</sup> Feb 1854  
 A1 per G. W. C. W. S.



© 2021

Lloyd's Register  
Foundation



REPORT OF SURVEY FOR REPAIRS.

18

*Doelme*

12429



© 2021

Lloyd's Register  
Foundation