

Completion of the *Lacbe Survey* 12832
REPORT of SURVEY for REPAIRS.

No. *12832* Survey held at *Liverpool* Date *Sept. 2* 1854
 on the *Ship Ocean Monarch* Master
 Tonnage *180 1/4* Built at *Lacbe* When built *1854*
 By whom built *Baldwin & Co* Owners *Chas E Levy & Co*
 Port belonging to *Lacbe* Destined Voyage *Liverpool*
 If Surveyed Afloat or in Dry Dock *in 99 ft afloat*

Last Survey, No. Port Classed

REPAIRS *Has been staid in the graving dock & had put to the Hold beams 29 pair of iron hanging knees 28 pair of which are long ones she had originally 1 pair of wood hanging knees in consequence of the wood hanging knees to deck beams being short she has had 4 pair of iron standing knees to hold beams she has to the deck beams 30 pair iron hanging knees & had originally 5 pair of wood hanging knees there are two deck beams aft of Hold beam to which more can be applied to advantage*

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats <i>11 on 15 3 others</i> <i>Upfy Good</i>
Upper Deck Beams & Fastenings	Timbers of the Frame <i>Good</i>	Masts, Yards, &c.
Lower Deck Beams & Fastenings <i>Good</i>	Keelsons	Sails <i>1 full set of the extra span</i>
Plank sheers	Clamps and Shelves	Anchors No. of <i>3</i> <i>48-1-4</i> <i>49-3-0</i> <i>55-2-4</i> <i>1 str 16-3-0</i> <i>2 str 8-2-0</i> <i>4-1-0</i>
Sheerstrakes	Ceiling	Cables <i>300</i> <i>2 1/8</i> <i>90 per 1/4</i>
Topsides	Rudder	Hawsers and Warps <i>90-12</i> <i>90-10</i> <i>90-7 1/2</i> <i>90-6 1/2</i>
Wales	Copper <i>Single bottom</i> <i>When put on</i>	Standing & Running Rigging <i>Good</i>
Plank (Bottom) and Counter		

General Observations and Opinion, *I find in an excellent condition fit for the safe conveyance of dry & perishable cargoes to & from all parts of the world & should in my opinion be classed as previously recommended 7 A 1*

The Amount of Fee.....£ - - - is received by me, *G W Mearns*
 Special..... *5* *5* *9/9/54*

Certificate (if required) *Grant*
 Committee's Minute *12th Sept* 1854
 Character assigned *7 A 1*



Dean Howard

1832



© 2021

Lloyd's Register
Foundation