

Completion of Quebec Report No. 253, & Change of Owners &c

REPORT of SURVEY for REPAIRS.

No. 14313 Survey held at Liverpool Date Jan 22 1857
on the Ship Scotia Master Jurcan
Tonnage 970 Built at Quebec When built 1856
By whom built 921 Owners Hamilton Adam & Co
Port belonging to Greenock Destined Voyage Calcutta
If Surveyed Afloat or in Dry Dock In & Afloat

Last Survey, No. _____ Port _____ Classed _____

REPAIRS

At this time 20 Deck Beams 28 Pairs of Iron hanging knees 23 Pairs of them Staple Standard knees taking the Hold Beams as well, all the beams have hanging knees where practicable. 20 Hold Beams 25 Pairs of Iron Rider knees taking two bolts in a substantial part of floor, those against the Porters and Breasthooks excepted. One Pair of Iron Riders in middle of Main hatch, to one beam aft a hanging knee cannot be properly put. 26 Beams in all. One Iron Breasthook. The upper Deck Beams are sufficiently secured independently of the Waterways.

11 Strakes of Woodsheathing on felt on the Wales for Protection fastened with Copper Nails.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps 2 of Metal & 2 Bridge with lead
Comings	Transoms, Pointers, and Crutches	Boats 3
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails well found
Planksheers	Clamps and Shelves	Anchor No. of 3 Bcs. St & Rds
Sheerstrakes	Ceiling	Cables complete, 210 ft of 1 3/4 inch supplied
Topsides	Rudder	Hawsers and Warps sufficient
Wales	Copper 7 Metal When put on recent time	Standing & Running Rigging good
Plank (Bottom) and Counter		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Appears in an efficient state and I have not seen any thing to prevent her blowing & as recommended by the Quebec Surveyor

The Amount of Fee.....£ 1 : : : is received by me,

Special..... 5 : 5 : : 23/1/57

Certificate (& required) Quint

Committee's Minute 27th January 1857

Character assigned 7.12



© 2021

Lloyd's Register Foundation

"Scotia" 14313



© 2021

Lloyd's Register
Foundation

CRE/pw/Q8C1138/7