

Read Jan'y 22<sup>nd</sup> Amst 26<sup>th</sup> 1774

New Wood vessel "Roach IV" to be built  
under special survey by Mr J. Smit  
at Slikkerveer.

A sketch of the Midship Section is  
submitted by Mr. Loos.

Dimensions 195 x 41.8 x 27.4

Proportions Length under 5 Breadth x 8 Depth.

This vessel is to be built on the same  
principles as the Ship "Liberaal" classed  
A.1 for 9 yrs. viz with large moulding  
small siding, and close spacing of frames -  
very heavy shelves and clamps and inside  
planking - large iron keelsons and bidge  
keelsons - and iron upper and lower deck  
beams. By the rules this vessel  
should have orlop beams - but as  
there are two strakes of heavy clamps  
where the orlop beams would be fitted  
and in consideration of the heavy inside  
planking and strong keelsons it is  
submitted that if the vessel is built  
in accordance with the sketch of midship  
Section, similar to the two vessels referred  
to viz the "Voorlichter" and "Liberaal" and  
in other respects in accordance with the  
rules and to the satisfaction of the local  
surveyors, she will it is considered be  
worthy of being classed A for a term of  
years to be regulated by her materials and  
fastenings.

B.M.  
26/1/74

26/1/74



© 2018

Lloyd's Register  
Foundation