

General Committee Minutes

29/6/83

Provided she be specially  
summed and found in  
good condition the  
Committee will be  
prepared to raise her  
Class to 13 A.I.

9 & 12 yrs Mat  
C-F Sailed

A.M.

Ltr to Fal 29/6/82



© 2021

Lloyd's Register  
Foundation



Wood Schooner "Trevellas", 121 Tons, (No. 478 in the Register Book) built in 1876 - 7mo. and classed 12 A1 "cf." "Salted". "9 & 12 yrs mat."

This vessel is about to be placed <sup>at Falmouth</sup> under Survey for Half Time and the Society's Surveyor requests to be informed if the vessel is eligible for an additional year in classification.

On reference to the First Entry Report it is found that the only 9 years material in the vessel is confined to the middle line keelsons. The whole of the frame, stem, stern post, aprons, knight-heads and hawse timbers are of English Oak - 12 years material; the beams, plank sheers, sheerstrakes and topsides and part of the Wales and blackstrakes are also of the 12 years grade, and the remaining materials are of the 10 years grade and above.

The workmanship is reported to be "very good".

It is respectfully submitted that in view of the very large proportion of 12 years material and the small amount of 9 years material, in the construction of this vessel, and the satisfactory quality of the workmanship, provided she be specially surveyed as proposed and be found in good and efficient condition and be favorably reported upon on completion, she will merit the favorable consideration of the Committee to be raised under the Mixed Material Rule, to the 13 A1 Class, as follows:

9 years - Table A  
2 years under the Mixed Material Rule  
1 year Salting  
1 " Metal fastening  
13 A1

"9 & 12 yrs mat"  
"cf." "Salted"

27/6/82  
Lloyd's Register  
Foundation  
© 2021