



Wreath Quay Iron Works.

Sunderland Feb 15 1864



Masts & Yards
for Ship
"Caruatic"
built by Messrs W. & A. Legg.

Foremast to the above section
length 44' 9" { Dia at Keel 21 Inches
" " Deck 26 "
" " Rounds 21 1/2 "
" " Head 14 1/2 "



Foremast. Bowsprit & Yards to
section.

OVER

Length of
Dia at

44' 3"
Dia at Deck 25"

" " Round 20 1/2 " " Head 16 1/2

Length of Bowsprit 29' 6"
Dia at Bottom 18 1/2" Dia at Top 20"
Dia at Middle 24"

Plates 1/16 x 3/8" manufactured by
The Palmer Shipbuilding & Iron Co.
2 Yards 70ft long. (Steel)
Dia at ends 4" Dia at Middle 16"

Steel Plates 7/16 - 1/4 - 3/16 & 1/8 "
Manufactured by John Brown & Co
Sheffield.

Butts Triple Rivetted & Seams
Double Rivetted

Masts doubled at Deck and Yards at Sails
Thos. W. & A. Legg