



Mast Length $64-10 \times 18 \times 23 \times 15\frac{1}{2}$ Keel Deck Head
 Mainmast " $70-10 \times 18\frac{1}{2} \times 23\frac{1}{2} \times 16$
 Bowspriet " $32-0 \times 19 \times 22\frac{1}{2} \times 18\frac{1}{2}$

All Seams & Butts planed
 " Seams single & Butts double rivetted
 Angle Irons ($3 \times \frac{3}{8}$) running full length
 of masts & Bowspriet
 Plates ($\frac{3}{8}$ & $\frac{7}{16}$ thick) of Best quality
 & Angles Best quality
 & Plates made by Palmer. Shipbuilding
 & Iron Co (Ld),



© 2021

Lloyd's Register
Foundation

SLD938-0120