

Steel Boilers to be made by Mess^{rs} P. Richardson & Sons
 of this Port for vessel h.^o 228 building by
 Mess^{rs} J. L. Thompson & Sons, Sunderland

| | | | |
|----------------------------|--|-----------------------|--|
| Shell | $\frac{260 \times 906 \times 85}{132}$ | = 151 lbs. | |
| Stays (long ^t) | $\frac{4.91 \times 7500}{15^2 \times 14}$ | = 163 lbs. | ^{175 lbs.} pitch altered. <u>181.</u> |
| Screw stays | $\frac{1.48 \times 8000}{8^2}$ | = 185 lbs. | |
| End plates | $\frac{140 \times 16^2}{15^2}$ | = 159 lbs. | |
| Combustion Chambers | $\frac{120 \times 9^2}{8^2}$ | = 151 lbs. | |
| Furnaces | $\frac{89600 \times .625^2}{5.75 \times 33}$ | = 184 lbs. | |
| " | $\frac{8520 \times 625}{33}$ | = 151 lbs. | |

H. Stoddart

5.44.84

SLD955-0276