

Tracing of Meredith Patent Boiler

14-6 high x 6-9 with 126-3 Tubes

Working pressure 80 lbs

Scale 1" = 1 foot.

Longitudinal seams in shell Lap joints
Double rivetted $\frac{13}{16}$ holes $2\frac{13}{16}$ pitch
rest of Boiler single rivetted
 $\frac{13}{16}$ holes $2\frac{1}{2}$ pitch

3 = Stay tubes $\frac{1}{4}$ thick tapped into CC and Rivetted Double Nuts on front end.

SS "Silun"
Sunderland report
No 16876.

SLD986-0001



© 2021

Lloyd's Register
Foundation