

Bre "W. A. Palmer" 471 tons, built under
the survey of Mr. Coffey at Rochester N. B. and
recommended to be classed 9A1.

Dimensions: $138.3 \times 32.4 \times 12.8$

Proportions 10.8 Sepths in Length.

From further information now received it appears
that this vessel has a raised quarter deck, and that she
has been strengthened longitudinally to compensate
for her extreme proportions, and also at the breast, to
the satisfaction of the Surveyor and appears to be worthy
the favorable consideration of the Committee to be classed
9A "Sailed" as recommended.

With respect to the Equipment supplied to this
vessel, it appears that the 1st Redge is smaller than given in
Table 22, but the Stream Anchor & Small Redge are much larger.
The Chain cable is $1\frac{1}{16}$ " instead of $1\frac{1}{8}$ " but only 240 fms. are
supplied in lieu of 240 fms, and the Stawpers & Warps are
considerably smaller than required by Table 22. It is
submitted that under these circumstances the vessel
does not appear to be eligible for the Figure 1 for Equipment



© 2021
J.H.

Lloyd's Register
Foundation
30/11/82

Lib. 18