

Steel Boilers to be made by Messrs J. Richardson & Sons
 Hartlepool of vessel h^o 223 building by Messrs J. L. Thompson
 & Sons Sunderland.

Shell	$\frac{260 \times 1.09 \times 85.3}{160}$	= 151 lbs.
Main Stays	$\frac{5.41 \times 7500}{15.875^2}$	= 161 lbs.
Side "	$\frac{1.48 \times 8000}{8^2}$	= 185 lbs.
End plates	$\frac{140 \times 16.5^2}{15.875^2}$	= 151 lbs.
Combustion Chambers	$\frac{120 \times 9^2}{8^2}$	= 151 lbs.
Furnaces	$\frac{4000 \times (7.5 - 2)}{36}$	= 152 lbs.

Subd
 11/18/87

© 2021
 J. Stoddart
 Lloyds Register
 Foundation

STK915-0253