

The undersigned do hereby certify to whom it may concern that the rebuilding of the Smack "Mary" of Oyster Pt. Inds Register is as follows

New English Elm Keel all fore & aft ^{14 by 10 New}
 English Oak Deadwood foreward & aft. New English Oak
 Stern, Apron, Stern post, Knight Heads, Nausepieces, four
 Hooks foreward, two Transoms, two Fashion pieces, two
 Main Transom knees, two Quarter Timbers, eight Stern timbers
 sixteen English Oak floors, thirty three first footlooks, thirty
 six second footlooks, sixteen Cant timbers aft, sixteen
 Cant timbers foreward, One Ambrace & eight Vot timbers,
 & twenty eight Chocks, New English Oak Nelson all fore & aft
 11-1/2 inches square all new English Oak upper Deck, Main
 Knees, Carlings, Ledges, Partners of the Mast, Comings
^{16 by 6} all new Watets, Carling & Ledges all new Deck all
 fore & aft of ^{2 1/2} American Pine, all new English Oak
 Stanchions, Rails, Saffle rail, Marping Chocks, Mastlars
 Miths & Wall Miths and Knees, new English Oak Horse and
 Knees and Riding Chock, Moulder & Filler, New Bulwarks
 all fore & aft, New Compassion & Keylight, Cabin, Bulkheads
 & Pumpwells, New Cheeks and Brackets to the Mast

1866 feet 5 inches of Oak timber for Sunders, Masts, Knees, &c.
7813 feet 8 inches of ^{1 1/2} Oak for Waterways, Stanks, keels, & sheer truss
Jopsticks, Blackshakes & Males and upper Deck clamps
2093 feet of 2 1/2 Oak for Planking outside & Ceiling 1177 feet
of 2 & 2 1/4 English Oak for Ceiling, 96 feet of 3 1/2 Inch English Oak for
Blackshakes inside, 382 feet of 4 1/2 English Elm for Plank
shakes outside, 4480 feet of 2 1/2 Inch English Elm for planks
bottom, 106 feet of 4 Inch Oak for Nails

New Plates and Maces, Dove tails, Shores foreward & Aft
Chain plates, 10 Iron Diagonal knees & 2 Iron Pumps
& Cater store & nearly all new blocks and a new Main V.
and Topmast

Exeter Sept^r 23rd 1884
Richard Potter



© 2021

Lloyd's Register
Foundation