

7.3.96
7.4.96

Midship Section. S.S. "Siria". 1949. Three Deck Rule. + 100 A1 Lloyd's (Steel).

22 / 1 / 6
II.

Bridge Deck.

Upper Deck.

Main Deck.

Equipment.

Lower Deck.

Principal Dimensions 400' x 48' x 33'

Numericals

1/2 Breadth	24'
1/2 Girth	51' 0"
Depth per rule	34' 0"
	109' 0"
	7' 0"
frames number	52' 0"
Length per rule	400'
Plating number	= 4114' 00"

Proportions.

Breadth to Length	5:33
Depth to	11:70 upper Deck.
Depth to	15:93 main Deck.

Scale: 1" = 1 foot.

Spacing of frames 25 inches.

- frames 6" x 3 1/2" x 3 1/2" x 1/2" for 1/2 length amidship ends 1/2"
- frames at ends 6" x 3 1/2" x 1/2" x 1/2"
- Reversed frames 4 1/2" x 3 1/2" x 1/2" x 1/2"

Forgings.

Stem bar	11 1/2" x 3 1/2"
Stem frame	11 1/2" x 7 1/2"
Distance head	10"
Distance heel	5" x 5"
Diagonal plates	5"

Double angles 4 1/2" x 3 1/2" x 1/2" x 1/2"

Diamond plate 30" x 24" x 1/2" x 1/2"
angles 3 1/2" x 3 1/2" x 1/2" x 1/2"
intercostal plate 22" x 10" x 1/2" x 1/2"

Diamond plate 30" x 24" x 1/2" x 1/2"
angles 3 1/2" x 3 1/2" x 1/2" x 1/2"
intercostal plate 22" x 10" x 1/2" x 1/2"

Double angles 4 1/2" x 3 1/2" x 1/2" x 1/2"

See 6" x 4" x 1/2" x 1/2"
Double plate 10" x 1/2" x 1/2" x 1/2"

© 2020

Arsenale del Lloyd An. - febbraio 1949 - Lloyd's Register Foundation

TK1155-0009

Grudship Section

L.L. 'Yreito'

Yreito 344.



© 2020

Lloyd's Register
Foundation

TR 1132-2009