

Messrs. Harland & Wolff's Yard Nos. 1016 & 1017.

Amended plan of fore body columns and girders
submitted by the Belfast Surveyors.

It is submitted the Surveyors be informed that the
scantlings and arrangements as shewn and amended will be
approved, provided they be carried out to their satisfaction.

They should also be informed with reference to the
final paragraph of the Builders' letter that the thickness of
the bulb angle stiffeners on the floors and intercostals was
increased on account of the loads to be carried by the pillars
and to be in conformity with the usual practice for stiffeners
under pillars of this size. In view of the Builders'
statement, however, regarding their previous vessel and as the
material has been delivered, the stiffeners might be accepted
as proposed, except those under the pillar on frame 37, where
it is considered these stiffeners should be fitted of the
increased thickness, or equivalent arrangements made, having in
view the very large load carried by this pillar.

Pi. 8. 6. 38
Am. 13. 6. 38
1 pla

J.K.B.
13. 6. 38. *W.J.*

Plan to be returned after mtg.



© 2015

Lloyd's Register
Foundation
W100-0103