

S.S. "W I N D I N G \_ G U L F"

QUESTIONS ENTITLING VESSEL TO SPECIAL ALLOWANCE:

- 1- Are hatches steel throughout? . . . . . Yes
- 2- Are bulwarks open 50%? . . . . . Yes
- 3- Are vent pipes at least as high as Bulwarks and specially strong, and are means of closing same provided? . . . . . Yes
- 4- Is a gangway fitted to enable crew to reach their quarters? . . . . . Yes
- 5- Any other items? Machinery casing sills 24" high.

ALLOWANCE FOR SPECIAL TYPE:

Summer Freeboard as Freighter	92.50 ✓
Summer Freeboard as Tanker	<u>84.58</u> ✓
Difference	7.92 ✓
2/3 Difference	5.28 ✓
Summer Freeboard as Freighter	92.50 ✓
Less allowance for Special Type	<u>5.28</u> ✓
SUMMER FREEBOARD AS SPECIAL TYPE	87.22 ✓



© 2020

Lloyd's Register  
Foundation

W1002-0065