

aphic Address ENGINEER, COPENHAGEN

Translation of Cablegram

Sent to the Surveyor at COPENHAGEN

respecting the steamer "SAINT JAN"

e 17.6.07

Time

SAINT JAN

(Vessel's name).

DAIRYING

DALIVUM

DAMNOST

DANTUM

DAPECHE

DAPPLIED

DARKNESS

The freeboard assigned is 2 ft. 3 $\frac{1}{2}$ inches from top of statutory deck line to centre of disc.

The statutory deck line is 1 $\frac{1}{2}$ inches above iron steel wood deck at side.

Corresponding to a freeboard of ft. inches
measured from top of statutory deck line inches
above top of iron steel wood part awning deck at side.

The fresh water line is 5 inches above centre of disc.

The Indian Summer line is 3 $\frac{1}{2}$ inches above centre of disc.

The Winter line is 3 $\frac{1}{2}$ inches below centre of disc.

The Winter North Atlantic line is 5 $\frac{1}{2}$ inches below centre of disc.



© 2020

Lloyd's Register
Foundation

Total ..

Length of Ship

Corresponding n