

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD. STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey *San Francisco*
Date of Survey *while building*
Name of Surveyor *A.P.W. Hob.*

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
<i>S.S. "ACME"</i>	<i>San Francisco U.S.A.</i>	<i>214173.</i>	<i>6898.81.</i>	<i>1916.</i>	<i>100 A.1. "Carrying Petroleum in bulk" (Class contemplated)</i>

Registered Length on Loadline.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
<i>435.0</i>	<i>435.0</i>	<i>52.0</i>	<i>31.58</i>	<i>6350.0</i>
		Frame Depth ✓	Ceiling ✓	Peak
		Rule " ✓	Sheer + <i>35</i>	Tanks

efficient of fineness..... *8162.813*
modification necessary {
[Para. 4 (a) to (e)]*
efficient as corrected *81*

Sheer { Stem..... *88* } *133* ÷ 2 = *66.5* ...Mean *53.50*
 { Sternpost *145* }
Sheer at 1/2 of the length from { Stem *49* } *73* ÷ 2 = *36.5* ...Mean *35.7*
 { Sternpost *24* }
Standard mean Sheer *36.5* ÷ *55* = *66.36*
Standard mean Sheer [Table, Para. 18] *32.1* Correction
Difference..... *4.4* ÷ 4 = *1.1*
If limited as Para. 18 (f)..... *-1*

Rise in Sheer { At front of bridge house..... ✓
from amidships {
Para. 18 (e)] { At after end of forecastle ✓
Fall in Sheer }
Para. 18 (d) } ÷ 2 =
Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS :—
Freeboard, Table C..... *5' 9 1/2*
Correction for Length, if required (Para. 12, 13, and 14) *+ 3*
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) *9' 7*
Difference *3' 6 1/2*
Percentage as below..... *24.88*

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) *- 10.57*
Allowance for Deck Erections *- 10 1/2*

	Length.	Length allowed.	Height.
Forecastle.....	<i>42.0</i>	<i>42.0</i>	<i>7' 6</i>
Bridge House	<i>50.0</i> (<i>then ends</i>)	<i>25.0</i>	"
† Raised Qr. Dk.....	✓	✓	✓
Poop.....	<i>106.25</i>	<i>106.26</i>	"
Total	<i>198.25</i>	<i>173.25</i>	
Length of Ship	<i>435.00</i>	<i>435.00</i>	<i>= 398.2</i>

Corresponding percentage {
(Para. 12, 13, or 14) } *24.88*

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, *Wood* (Iron) Deck :—
Fresh Water Line above centre of Disc
Indian Summer Line " " "
Winter Line below " "
Winter North Atlantic Line " " "

† If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abt amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one eighth of the vessel's length from stem and sternpost.

Moulded Depth as measured..... *33' 6*
33' Wood dk.
33' 2 1/2 less stringer.
NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.
Length of Ship on Loadline..... *435.0*
Length in Table *398.5*
Difference *36.5*
Correction for 10ft., Table A. *1.64* Table C. *.8*
× Difference divided by 10 *5.98* (if required,) *2.99*
If 1/10ths length covered divide by 2 *+ 6* *+ 3*

CORRECTION FOR IRON DECK.
Proportion covered, if less than 1/10ths length covered *allowed for in*
Thickness of usual wood deck, less stringer *moulded depth.*

CORRECTION FOR ROUND OF BEAM.
Breadth at Gunwale amidships..... *55.0*
Round of Beam *12*
Normal round..... *13 3/4*
Difference *13 3/4 ÷ 2 = 6.75*
Proportion of Deck uncovered (Para. 19) *3445* = *+ 1 1/2*

Freeboard, Table A *9' 1*
Correction for Sheer *- 1*
Correction for Length *+ 6*
Allowance for Deck Erections *10 1/2*
Correction for Round of Beam..... *+ 1 1/2*
Correction for fall in Sheer (if any).....
Correction for Iron Deck (if required) *allowed for in moulded depth.*
Additions for non-compliance with provisions of {
Para. 11 (d) and (e) }
Other Corrections (if any)

Winter Freeboard *8' 8*
Summer Freeboard *8' 2*
Indian Summer Freeboard *7' 8*
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the *wood or* iron deck with side. *+ 1 1/2*

Winter Freeboard from deck line *8' 9 1/4*
Summer " " " " *8' 3 3/4*
Indian Summer " " " " *7' 9 3/4*
N. A. Winter " " " "

Winter Freeboard from deck line *8' 3 1/2*
Summer " " " " *6 1/2*
Indian Summer " " " " *6*
N. A. Winter " " " " *6*

† State dimensions of freeing port area on back of this form.
The Surveyor should state whether the fall in sheer as reported is measured relatively to the line of keel or to the water line. If measured relatively to the water line the vessel's survey, and also the usual load draft should be reported.

all the Frames extend to the top height in the Poop? *Longitudinal framing.*
 To what height do the Reverse Frames extend? *Longitudinal framing.*
 Has the Poop or Raised Quarter Deck an efficient Iron Bulkhead at the fore end? *yes.*
 Give particulars of the means for closing the openings in Bulkhead *no openings.*
 Is the Poop or Raised Quarter Deck connected with the Bridge House? *no.* Has the Bridge House an efficient Bulkhead at the fore end? *no.*
 Give particulars of the means for closing the openings in Bulkhead
 What is the thickness of the Bridge Front plating? and Coaming plate? *open ends.*
 Give scantlings and spacing of the Stiffeners
 Are bracket plates fitted at each end of the Stiffeners? *yes.* Are hor'l. brackets fitted connecting Bridge Bulk'd. with Bulwarks? *yes.*
 Has the Bridge House an efficient Iron Bulkhead at the after end? *open ends.*
 How are the openings closed? *yes.*
 Is the Forecastle at least as high as the main or top-gallant rail? *yes.* Has the Forecastle an efficient Iron or Wood Bulk'd. at after end? *no. open*
 Are the Engine and Boiler openings covered by a Bridge, Poop, Raised Quarter Deck, or enclosed by a Strong Iron or Steel Deckhouse? *yes. Poop Id. Coaming 48. Plating 44. Stiffeners 10 x 3 1/2 x 625*
 If the openings are not so protected are the exposed parts of the Casings efficiently constructed? *yes.*
 Give thickness of plating; scantlings and spacing of Stiffeners *spaces about 30 apart bracketed top & bottom*
 What is the height of the exposed Casings? *yes.* Are suitable means provided for closing all openings in them in bad weather? *yes.*
 Are the Weather Deck Hatchways efficiently constructed and at least equal to the requirements of Section 28 of the Rules for 1904-5? Give particulars below:— *yes.*


Position and Size.		No 1. 10' 0" x 10' 0"									
Item.		Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.
COAMING.	Height above top of DECK	24"		18 oil hatchways.	6' 0" x 4' 0"						
	Sides.....	44"									
	Ends.....	44"		10			4' 0" x 2' 6"				
SHIFTING BEAMS OR WEB PLATES.	Number.....	one.		Coamings.	8 x 3 1/2 x 1/2" angles.						
	Section and Scantlings.....	plate 30.									
	Material.....	angle 3 x 3 x 40.			with covers 38 efficiently stiffened.						
* FORE AND AFTERS.	Number.....										
	Section and Scantlings.....	✓									
	Material.....										
HATCHES Thickness.....		3'									
Remarks.....		solid									

* The depth of Fore and Afters should be stated from the underside of the hatches in all cases.
 (If the sill of the lowest side scuttle will be less than 6 inches above the Indian Summer Load Line if assigned under the tables, state vertical distance from top of deck at side amidships to lower edge of lowest side scuttle.)

The following information is to be given in all Cases of vessels dealt with under Paras. 11, 12 (under 15 feet Moulded depth) and under Shelter Deck Rules.
 What is the thickness of the Bridge Sheerstrake? *Strake between Main and Bridge Sheerstrakes?*

Delete the words { The Crew are, are not, berthed in the bridge house.
 that do not apply { The arrangements to enable them to get backwards and forwards from their quarters are, are not satisfactory.

Length of Bulwarks in well					
Area of Freeing Ports required by Para. 11 (e) each side of vessel				=	Sq. ft.
Ft.	Tenths.	Ft.	Tenths.	No.	
	x		x		
	x		x		
				Freeing Ports (each side of vessel)	= Sq. ft.
				Total deficiency or excess	= Sq. ft.



Show hereon line of Floors or Tank Top with position of any Breaks in same; also height of Peak Tank tops, &c., &c.

State any special features in the construction of the Vessel *Please see Preliminary report No 2289 & Secy's letter of 24/3/16. This vessel is now on her first voyage to Shanghai & it is the owner's intention to have the vessel marked on her return here.*
 Owners *The Standard Transportation Co of Delaware.*

Address *New York.*
 Fee: *\$ 40* Applied. *Expn Received by me*