

Lloyd's Register of Shipping

CHARACTER.
* for Special Survey.
Date of last Survey and of
Periodical Surveys.

m.12.42.

V.G.

25 OCT 1943

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME

"HOPESTAR"

REPORT

Lth.

21059

Nwc.

No. 101582

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

For conditions of class see previous endorsement.

The LEITH Surveyors report the vessel afloat and on account of leakage in the deep tank repairs to a fractured bulkhead plate.

The NEWCASTLE Surveyors ^{earlier} report the vessel placed in dry dock, bottom coated and minor repairs effected.

Cargo battens had been fitted to all holds and 'tween decks at some previous time.

The notation of "Cargo Battens not fitted" should now be deleted from the Register Book.

EXTENSION OF W.T. BULKHEADS IN SHELTER 'TWEEN DECKS.

Four additional watertight bulkheads suitably stiffened have been fitted in the shelter 'tween decks over the main bulkheads. Scuppers have been led to the bilges with the exception of ^{those} abaft the deep tank which will be completed at the termination of the present voyage. ~~and~~ The bulkheads have been satisfactorily hose tested.

IT IS SUBMITTED the vessel be continued as classed with record of docking survey 9,43 subject to indented shell plating etc (p.s.) in way of No.2 hold, and indented bottom plating etc (p & s.f) being permanently repaired at the first convenient opportunity and to scupper pipe (p & s) abaft deep tank being led to the bilges at the end of the present voyage.

9,43 Nwc. subject

Delete from RB. "Cargobattens not fitted."

GMB

21.10.43

T.O. CLOSED. (W.E.)



© 2020

Lloyd's Register
Foundation

entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."