

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR
AWNING DECKS.

Port of Survey

Date of Survey

Name of Surveyor

Ship's Name.

Port of Registry
and Nationality.

Official
Number.

Gross
Tonnage.

Date of Build.

Particulars of Classification.

Number in Register Book

Registered
dimensions from
Ship's Register.

LENGTH.

BREADTH.

DEPTH.

UNDER DECK
Tonnage.

Moulded Depth as measured ... 34-4 Main Deck.

32-10 Sheels
Spar or Awning Deck.

42

Length on

Frame Depth

Ceiling

Peak

LOADLINE

Rule

Sheer

Tanks

CORRECTED
DIMENSIONS.

477.09

Co-efficient of fineness

Any modification necessary

[Para. 4 (a) to (e)*]

Co-efficient as corrected

75

Allowance for strength in excess of Lloyd's rules =

State particulars—

CORRECTION FOR LENGTH:—

Length of Ship on Load Line.... 477.09

Length in Table..... 412

Difference..... 65.09

Correction for 10ft..... 8

× Difference ÷ 10 = 5.2072

+ 5 1/4

Height of 'Tween Decks..... 8-6

(From top of beam to top of beam at side)

Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table C..... 9-3 1/2 - 3-2

Correction for Length.....

Correction for Height of 'Tween Decks in Spar-decked Ships.....

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required.....

Other Corrections (if any).....

Sheer at Stem at 1/2 length from Stem

Sternpost... " " " Sternpost...

Drop in Sheer abaft amidships.....

Round of Spar-deck Beam.....

" " Main-deck "

Length × Height. State if open or closed at ends.

Forecastle ×

Bridge..... ×

Poop..... ×

Winter Freeboard..... 14-9

Summer Freeboard 14-2 1/2

Indian Summer Freeboard.....

N. A. Winter Freeboard.....

Correction necessary because clearside amidships measured
in accordance with the Statute is not taken at inter-
section of the wood or iron deck with side

Winter Freeboard from Deck Line

Summer " " "

Indian Summer " " "

N.A. Winter " " "

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Iron) Deck:—

Fresh Water Line above centre of Disc ...

Indian Summer Line " " " ...

Winter Line below " " " ...

Winter North Atlantic Line " " " ...

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full
scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.
All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-
decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.
* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.