

Y. S. S. "Port-Thomas."

Guide shoes reinstalled.

Valve spindles skimmed true & bushes renewed.

L. P. cylinders fitted with new piston rings.

The H. P. piston valve rings renewed.

Air pump liners skimmed true & buckets renewed.

Feed pump plungers tried in lathe.

Two main condensers & two Drysdale air pumps fitted and
two new Wau's lubricating oil pumps fitted. 10" x 9" x 24".

The main boilers examined in their entirety, found
in good condition & their safety valves adjusted,
under steam to above working pressure

working.

Vessel placed in dry-dock, & propellers, all sea
connections & fastenings examined.

Both screwshafts (C.L.) drawn in, examined, found sound
& refitted.

Two new L. P. Bauer-Wach turbines have been
fitted to work in conjunction with the
existing machinery & have been securely
fitted on board the vessel, tried under full
working conditions & found satisfactory.


Final entry machinery report attached.

Sea trial attended & all found satisfactory.


Thos. A. Burgess. E. J. Hoddart.

St. No 3 due 1.30 Held. Machinery
overhauled. Crankshafts rebored. Low
Pressure (Bauer-Wach) turbines fitted
to each Main Engine.

It is submitted that
this vessel is eligible for
THE RECORD. + L.M.C. 9.29

S. 9.29
N.H.P. 986. 
25/10/29

Add to Machinery
notation "2 L.P. Turbines
with D.R. gearing and
hydraulic couplings."


25/10/29



© 2020

Lloyd's Register
Foundation