

Lloyd's Register of Shipping. 27 OCT 1941

Ship's Name "BENGLOE"

Official No. 137058

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

(1) 9" Port, (3) 12" diameter sidelights Starboard & 2 Port with dead lights fitted in poop.

(1) new ventilator fitted Port & Starboard on poop leading to poop 12" diameter coaming 30" x 7/20". Wood plug & canvas covers supplied.

Forecastle Bulkhead. Opening Port & Starboard fitted with storm board now plated over & steel hinged doors operated from both sides fitted sill 30".

Forecastle deck above accommodation now fitted with 2, 1/2" wood.

(1) 9", (2) 12" diameter sidelights with deadlights fitted Port & Starboard in forecastle.

Bridge Aft Bulkhead. Starboard side storm boards opening plated over and hinged steel door operated both sides fitted sill 24".

(2) 12" sidelights with deadlights fitted Starboard side bridge space.

New companion way fitted Starboard side of bridge deck leading to accommodation in bridge space efficiently constructed of steel 4'3"x 2'6", 7'4" high fitted with hinged steel door 26" x 60" operated from both sides, sill 18"

Geo R. Kouchiffé

H. K. 6/8/41

Noted
27/10/41