

# (LLOYDS REGISTER.)

G. R. 130  
Lloyds Register

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) J. S. B. T.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
137058	" Ardgoil "	11/1914 Greenock.
No., Date, and Port of Previous Registry (if any).		
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.
British	Steamship Single Screw	Port Glasgow
When Built.	1917	
Name and Address of Builders.		
William Hamilton & Co. Ltd. Port Glasgow		
Number of Decks	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel
Rigged	Schooner	Main breadth to outside of plank
Stern	Elliptical	Depth in hold from tonnage deck to ceiling at midships
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards
Galleries	none	Depth from top of beam amidships to top of keel
Head	none	Depth from top of deck at side amidships to bottom of keel
Framework and description of vessel	Steel Cargo	Round of beam
Number of Bulkheads	Six	Length of engine room, if any
Number of water ballast tanks, and their capacity in tons	Seven 2090 tons	

### PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel 10975 Tons. Ditto per inch immersion at same depth 42.66 Tons.

### PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple Expansion Inverted Cylinders	Engines. British	Engines. 1914	John G. Kincaid & Co. Ltd. Greenock	Three 27" 44" 73"	40"		266.46 2150 10 1/2 knots
No. of Shafts.	Particulars of Boilers.	Boilers. Do.	Boilers. Do.	Do.				
	Description..... Number..... Iron or Steel..... Loaded Pressure							

### PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	4928.18	On account of space required for propelling power	1701.73
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	122.85
Turret or Trunk		These spaces are the following, viz:—	
Forecastle	15.47	In Poop, in Deck Houses & Side Houses on Bridge Deck	
Bridge space (House in)	88.04	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop on Break	36.24	Cubic Metres	
Side Houses	93.47	Master's Accommodation 12.79	
Deck Houses	4.02	Chart Space 4.02	
Chart House		Wireless House 5.53	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	110.49	Boatwain's Store 36.80	
Excess of Hatchways	41.96	Waterballast Spaces 9.98	
Gross Tonnage	5317.90	Total	68.32
Deductions, as per Contra	1092.90		
Registered Tonnage	3425.00		1092.90

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 581.94 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 141.03 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle 42.75 ft. long, less hatchway 99.62 Tons  
Open Bridge Space 120.0 ft. long 456.00  
Less Round House, Engine & Boiler Casings, 96.35 } 359.65 Tons  
Coal shoot & Hatchways

Name of Master

Certificate of { Service No.  
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

"Ard" Steamers Limited, of 1, Cathcart Street, Greenock, in the County of Renfrew. Sixty-four shares.  
James Fulton, Junior, of above address, designated manager.

Dated 24th December, 1914.