

*Preliminary*  
**Lloyd's Register of Shipping.**  
SURVEYS FOR FREEBOARD.—STEAM SHIPS.

Index No. **30406**  
(For London Office only.)

ARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH  
TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR  
WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS  
CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey *Newcastle-on-Tyne*  
Date of Survey *7.5.23.*  
Name of Surveyor

Ship's Name. *without Leslie* Port of Registry and Nationality. *nos 529 130*  
Official Number. Gross Tonnage. Date of Build. Particulars of Classification. **100 A.I. Shelter Deck with Freeboard.**

REGISTERED LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
<i>450</i>	Frame Depth <i>11</i> Rule <i>7</i> <i>-67 4</i> <i>having fitted</i>	No. <i>20</i> Ceiling <i>+20</i> Sheer <i>+72</i> <i>Hank rises</i>	Peak Tanks
<i>450</i>			

Moulded Depth as *given* measured *31'-6"*  
Addition for Keel below base line for draught record *2 1/2* inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.  
Length of Ship on Loadline *450'*  
Length in Table *378*  
Difference *72*  
Correction for 10ft., Table A. *1.6* Table C. *✓*  
× Difference divided by 10 *11.52* (if required.)  
If *1/10*ths length covered divide by 2 *5.76* *+5 3/4"*

CORRECTION FOR IRON DECK.  
Proportion covered, if less than *1/10*ths length covered  
Thickness of usual wood deck, less stringer *3 1/2* *-3 1/2"*

CORRECTION FOR ROUND OF BEAM.  
Breadth at Gunwale amidships *59*  
Round of Beam *6.0*  
Normal round *14.75*  
Difference *8.75 ÷ 2 = 4.37*  
Proportion of Deck uncovered (Para. 19) *.023* *✓*

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A *8'-1 1/2"*  
Correction for Sheer *-6 1/2*  
*7-7*  
Correction for Length *+5 3/4*  
*8-0 3/4*  
Allowance for Deck Erections *-2-4 3/4*  
*5-8*  
Correction for Round of Beam *✓*  
Correction for fall in Sheer (if any) *✓*  
Correction for Iron Deck (if required) *-3 1/2*  
*5-4 1/2*  
Additions for non-compliance with provisions of Para. 11 (d) and (e) *✓*  
Other Corrections (if any) *✓*

Winter Freeboard *5-4 1/2*  
Summer Freeboard *6 1/2* *4-10*  
Indian Summer Freeboard *4-3 1/2*  
*N.A. Winter Freeboard* *✓*

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the ~~wood~~ steel deck with side. *+1/2"*

Winter Freeboard from deck line *5'-5"*  
Summer " " " *4'-10 1/2"*  
Indian Summer " " " *4-4*  
*N.A. Winter* *✓*

Freeboard recommended amidships from centre of Disc to top of Statutory Deck Line, ~~Wood~~ (Steel) Deck:—  
Fresh Water Line above centre of Disc *4'-10 1/2"*  
Indian Summer Line " " " *6 1/2*  
Winter Line below " " " *6 1/2*  
Winter North Atlantic Line " " " *6 1/2* *✓*

State dimensions of freeing port area on back of this form.  
The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

efficient of fineness *Block coefft = .75 25'-6" draft*  
modification necessary *given by builders*  
efficient as corrected *Assumed .76*

Stem *108*  
Sternpost *54* *162 ÷ 2 = 81* ...Mean *36 1/2*  
Stem *Assumed gradual*  
Sternpost *Mean*  
gradual mean Sheer *81*  
Standard mean Sheer [Table, Para. 18] *55*  
Difference *26* *÷ 4 = 6.5*  
If limited as Para. 18 (f) *-6 1/2"*

Rise in Sheer { At front of bridge house  
from amidships {  
Para. 18 (e) { At after end of forecastle *✓*  
Fall in Sheer { *nil* *÷ 2 =*  
Para. 18 (d) {  
length uncovered *Correction*

ALLOWANCE FOR DECK ERECTIONS:—  
Freeboard, Table C. *5'-0"*  
Correction for Length, if required (Para. 12, 13, and 14) *✓*  
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) *7'-7"*  
Difference *2-7*  
Percentage as below *92.7%*  
*Particulars scaled from blue print*  
Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) *28.7*  
Allowance for Deck Erections *-2-4 3/4"*

	Length.	Length allowed.	Height.
Forecastle	<i>382.5</i>	<i>379.63</i>	<i>8'-6"</i>
Bridge House	<i>16.0</i>	<i>✓</i>	
Raised Q. Dk.	<i>51.5</i>	<i>49.25</i>	<i>8'-6"</i>
Total	<i>450.0</i>	<i>428.88</i>	
Length of Ship		<i>10.56 1/2 Diff</i>	
Corresponding percentage	<i>92.7%</i>	<i>439.44</i>	
Para. 11, 12, 13, or 14		<i>450</i>	<i>= 977</i>

Freeboard recommended amidships from centre of Disc to top of Statutory Deck Line, ~~Wood~~ (Steel) Deck:—  
Fresh Water Line above centre of Disc  
Indian Summer Line " " "  
Winter Line below " " "  
Winter North Atlantic Line " " "

the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.  
vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.  
flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

© 2020

Lloyd's Register Foundation  
W1029-0065