

GENERAL DIMENSIONS	
LENGTH BETWEEN PERPS.	315'-0"
LENGTH OVERALL	328'-0"
BREADTH MOLDED	43'-6"
DEPTH MOLDED	27'-6"

LLOYD'S NUMERALS	
BREADTH MOLDED	43.50
DEPTH MOLDED	27.50
TRANSVERSE NO.	71.00
LENGTH BETWEEN PERPS.	315.0
LONGITUDINAL NO.	22365
DEPTH TO LENGTH	11.45
EQUIPMENT AS PER RULE	
PROP, BRIDGE & FORECASTLE	765
HOUSES ON PROP & BRIDGE	326
LONGITUDINAL NO.	22365
	23456

#### RIVETING NOTES

KEEL BUTTS - QUADRUPE BUTT LAPS - 1 RIVETS FOR 3/4" L. AMIDSHIPS, TREBLE RIVETED BUTT STRAPS AT ENDS; RIVETS SHEER STRAKE BUTTS - QUADRUPE BUTT LAPS - 1 RIVETS AMIDSHIPS, TREBLE RIVETED BUTT LAPS; 7/8 RIVETS AT ENDS AND QUADRUPE BUTT LAPS; 1 RIVETS AT PROP FRONT & BRIDGE ENDS

BALANCE OF SHELL - TREBLE RIVETED BUTT LAPS; 7/8 RIVETS

CENTER KEELSON - TREBLE RIVETED BUTT LAPS; 7/8 RIVETS

UPPER DECK STRINGER PLATES - TREBLE RIVETED BUTT LAPS; 7/8 RIVETS AMIDSHIPS, TREBLE RIVETED BUTT LAPS 3/4" RIVETS AT ENDS AND QUADRUPE BUTT LAPS; 7/8 RIVETS AT PROP FRONT & BRIDGE ENDS

TANK DECK STRINGER PLATES - DOUBLE RIVETED BUTT LAPS; 3/4" RIVETS

UPPER DECK PLATING - DOUBLE RIVETED BUTT LAPS; 3/4" RIVETS AMIDSHIPS, SINGLE RIVETED BUTT LAPS AT ENDS; 3/4" RIVETS STRAKE C TO BE TREBLE RIVETED BUTT LAPPED; 3/4" RIVETS & SINGLE RIVETED BUTT LAPPED AT ENDS; 3/4" RIVETS SEAMS; DOUBLE RIVETED LAPS; 3/4" RIVETS AMIDSHIPS, SINGLE RIVETED LAPS; 3/4" RIVETS AT ENDS

TANK DECK PLATING - DOUBLE RIVETED BUTT LAPS; 3/4" RIVETS

SEAMS - DOUBLE RIVETED LAPS; 3/4" RIVETS

TRANS & STRAKE PLATES - BUTTS & SEAMS DOUBLE RIVETED LAPS; 3/4" RIVETS

TRANSVERSALS - FOR RIVETING SEE MIDSHIP SECTION

PIPE & STR LONGS - 7/8 RIVETS SPACED AS NOTED IN MIDSHIP SECTION

DECK LONGITUDINALS - 7/8 RIVETS SPACED 6 DIAMETERS CENTERS

ALL OTHER RIVETING - TO BE AS ELSEWHERE NOTED IN SECTIONS OR IN ACCORDANCE WITH LLOYD'S RULES

#### GENERAL NOTES

NOTCHES IN TRANSVERSALS, WEBS & BEAMS TO BE WELL ROUNDED AT CORNERS AND NOT TO BE RAUGH FINISHED. BRACKETS ATTACHING LONGS TO BEAMS TO BE 1/4" THICK AT & BELOW TANK DECK & 1/2" THICK ABOVE TANK DECK. ALL BOTTOM BRIDGE & 10 RIVET BRACKETS TO BE FLANGED ON FACE

DRAINAGE HOLES IN BOTTOM LONGITUDINALS: 3" - 18" SPACED 30"

DIP BRACKET CLIPS ARE TO EXTEND FAR ENOUGH BEYOND BRACKET TO SECURE AT LEAST TWO MORE RIVETS FOR INFORMATION REGARDING SPACING SEE DETAIL OF LONG BRACKETS, SEE - PRG

"SOLITAIRE" B&B

TEXAS STEAMSHIP COMPANY

NEW YORK CITY  
CONSTRUCTION DEPARTMENT

HULL NO. 14

MIDSHIP SECTION AND BULKHEAD

SCALE 1/2" = 1 FT.

18TH JAN. 1917

LOHMEYER SYSTEM PATENT

Des. No. 111

