

Rpt. 13.

No. 13649

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report *22nd April 25* When handed in at Local Office *2/5* to *25* Port of *Antwerp* Received at London Office.....

No. in *Sup't* Survey held at *Hoboken, Belgium*. Date, First Survey *11th Feb 25* Last Survey *15th April 1925*
Reg. Book *89895* on the *S/S "JORDAENS."* (Number of Visits... *7*)

Built at *Hoboken*. By whom built *Antwerp Eng. Co. Ltd.* Yard No. *89*. Tons { Gross *1430*.
Net *✓* When built *1925*.

Owners *Compt. Char. Mar. Soc. Anon.* Port belonging to *Antwerp*.
Etalissements Belges

Electric Light Installation fitted by *Campbell & Isherwood, Soc. Anon* Contract No. _____ When fitted *1925*.

System of Distribution *Double wired. ✓*

Pressure of supply for Lighting *110 Volts ✓* volts, Heating _____ volts, Power _____ volts.

Direct or Alternating Current, Lighting *direct ✓* Power _____

If alternating current system, state frequency of periods per second _____

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off *yes ✓*

Generators, do they comply with the requirements regarding overload *yes*, are they compound wound *yes ✓*

are they over compounded 5 per cent. *yes*, if not compound wound state distance between each generator *✓*

Where more than one generator is fitted are they arranged to run in parallel _____, is an adjustable regulating resistance fitted in series with each shunt field _____

Are all terminals accessible and clearly marked *yes*, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited _____

Position of Generators *on Platform (starting platform)* Are the lubricating arrangements of the generators as per Rule *yes*

is the ventilation in way of the generators satisfactory *yes*, are they clear of all inflammable material *yes*

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators _____ and _____, are the generators protected from mechanical injury and damage from water, steam or oil *yes*

are their axis of rotation fore and aft *yes*

Earthing, are the bedplates and frames of the generating plant efficiently earthed *yes* are the prime movers and their respective generators in metallic contact *yes*

Main Switch Boards, where placed *above Dynamo*

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard _____

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes *yes*

are they protected from mechanical injury and damage from water, steam or oil *yes*, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards _____ and _____

are they constructed wholly of durable, incombustible non-absorbent materials *yes*, is all insulation of high dielectric strength and of permanently high insulation resistance *yes*

if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework *yes*, and is the frame effectively earthed *yes*

Are the following fittings as per Rule, viz.: — spacing or shielding of live parts *yes*, accessibility of all parts *yes*, absence of fuses on back of board *yes*, proportion of omnibus bars *yes*, individual fuses to voltmeter, pilot or earth lamp *yes*, connections of switches *yes*

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches *SP Switches*

for Dynamo & to circuits D.P. fuses

Instruments on main switchboard *1* ammeters *1* voltmeters _____ synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system *earth lamps*

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules *yes*

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule *yes*

Insulation of Cables, state type of cables, single or twin Single are the cables insulated and protected as per Tables III or IV of the Rules Table III

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 3%

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets yes

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound _____

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes

Support and Protection of Cables, state how the cables are supported and protected by galvanized steel pipes

If cables are run in wood casings, are the casings and caps secured by screws _____, are the cap screws of brass _____, are the cables run in separate grooves _____ If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements _____

Joints in Cables, state if any, and how made, insulated, and protected there are none

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas _____

_____ are their connections made as per Rule _____

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven _____

Navigation Lamps, are these separately wired yes, controlled by separate switch and separate fuses yes

are the fuses double pole yes, are the switches and fuses grouped in a position accessible only to the officers on watch yes

has each navigation lamp an automatic indicator as per Rule yes, are separate screens provided for the use of oil and electric side lights no

are separate oil lanterns provided for the mast head lights and side lights yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected no

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected no

_____ how are the cables led _____

_____ where are the controlling switches situated _____

Searchlight Lamps, No. of none, whether fixed or portable _____, are their fittings as per Rule _____

Arc Lamps, other than searchlight lamps, No. of none are their live parts insulated from the frame or case _____, are their fittings as per Rule _____

Motors, are their working parts readily accessible none, are the coils self-contained and readily removable for replacement _____

are the brushes, brush holders, terminals and lubricating arrangements as per Rule _____, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material _____

are they protected from mechanical injury and damage from water, steam or oil _____ are their axis of rotation fore and aft _____

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type _____, if not of this type, state distance of the combustible material horizontally or vertically above the motors _____ and _____

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule _____

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule _____

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings _____

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office _____

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No of	RATED AT			Revs. per Min.	DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amperes.			Fuel Used.	Flash Point of Fuel.
MAIN	1	3	110	27	400	Open type vertical engine		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	0.01462	7	0.052	27	12	rubber	lead covered & armoured
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS	14	0.00701	7	0.036	15	132.1		In steel pipes
	ENGINE ROOM	2	0.00455	7	0.029	9	5.5		lead covered & armoured
	BOILER ROOM	2	0.00455	7	0.029	9	6.2		" "
	WIRELESS								
	SEARCHLIGHT								
	MASTHEAD LIGHT	2	0.00194	3	0.029	1	140		Steel pipe
	SIDE LIGHTS	2	0.00194	3	0.029	1	60		Lead covered
	COMPASS LIGHTS	2	0.00194	3	0.029	0.5	20		Lead covered
	POOP LIGHTS								
	CARGO LIGHTS	2	0.00455	7	0.029	4	320		Steel pipe
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

CAMPBELL & KHERWOOD
 Societe Anonyme

Electrical Engineers. Date 18 April 25

[Signature]
 In administrateur.

COMPASSES.

Distance between electric generators or motors and standard compass 65 ft.

Distance between electric generators or motors and steering compass 60 ft.

The nearest cables to the compasses are as follows:—

A cable carrying 0.5 Ampères 5 feet from standard compass 3 feet from steering compass.

A cable carrying ✓ Ampères ✓ feet from standard compass ✓ feet from steering compass. ✓

A cable carrying — Ampères — feet from standard compass — feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power. *yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*

The maximum deviation due to electric currents was found to be *negligible* degrees on _____ course in the case of the standard compass, and _____ degrees on *negligible* course in the case of the steering compass.

THE ANTWERP ENGINEERING COMPANY S.A.C. S.A.

[Signature]
 General Manager.

Builder's Signature. Date 30 April 1925

Is this installation a duplicate of a previous case *No.* If so, state name of vessel ✓

General Remarks (State quality of workmanship, opinions as to class, &c. *The workmanship & materials are good.*

The installation has been fitted on board under special survey, & when tried under full working conditions, was found satisfactory.

The record of "Electric light," may, in my opinion, be made in the R.B. in the case of this vessel.

It is submitted that this vessel is eligible for THE RECORD. Elec. light.

[Signature]
 4/5/25

Total Capacity of Generators 3 Kilowatts

The amount of Fee	£ 78 = francs 760 =	When applied for,	2-5-1925
Travelling Expenses (if any) £	:	When received,	29.5.25

[Signature]
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

56,1243.—Transfer. (The Surveyors are requested not to write on or below this page for Committee's Minute.)