

# LLOYD'S REGISTER OF SHIPPING

PORT of Bremen

Augsburg, 4th. February, 1939.

Komm.180105.  
2xMU 1 B2, Form E.  
Lloyd's 225/a & b.  
Komm.180104  
1 x MU 2 A2, Form A.  
Lloyd's No. 226.

THIS IS TO CERTIFY That

XXXXXXXXX Heinrich Schneider XXXXXXXXXXXXX

the undersigned Surveyor to this Society did at the request of Messrs. August Neidig Sohne, Maschinenfabrik of Mannheim attend at their works at Mannheim -Industriehafen on the 1st & 2nd. February, 1939 for the purpose of testing and inspecting two lubricating oil-and one daily service pumps of the cog wheel type with the coupled electric motors to the order of Messrs. C. André & Co. Hamburg and intended for a vessel owned by Messrs. Hijos de E. d. la Rama, Iloilo/Philippines.

## Specification

Lubricating oil pumps	Daily service pump-
Makers Type & No.: 2 x MU 1 B 2/Form E.	1 x M U 2 A 2/Form E.
Quantity delivered: 2 x 4 tons/hour	1 x 5 tons/hour.
Delivery head: 0,7 and 4,8 atm resp.	2,5 atm.
Rev. per Min.: 1500 R.P.M.	1430 R.P.M.

The lubricating oil pumps and the daily service pump have been tested on the makers test bed during several hours and were found to be in safe and efficient condition during these trials and the results were found to meet the requirements of the order.

After bed test trial all pumps have been opened up for inspection and were found, so far as could be seen, to be in order and the workmanship to be satisfactory.-

After inspection all three pump casings have been submitted to internal hydraulic pressure of 2,5 and 10 atm. respectively and were found to be sound and tight when under test pressure.

For identification purposes the pumps have been marked as follows:

Lubricating oil pumps.		Daily Service Pump.
A.	B.	
Lloyd's Test. 2 atm.	Lloyd's Test. 10 atm.	Lloyd's Test. 5 atm.
No. 225/a	No. 225/b	No. 226.
H.K.S. 1.2.1939	H.K.S. 1.2.1939	H-K-S- 1.2.1939.

(Sgd.) H. SCHNEIDER  
SURVEYOR TO LLOYD'S REGISTER.



© 2021

Lloyd's Register  
Foundation

W103-0016