

COPY OF CERTIFICATE OF
INSPECTION AND TEST OF MATERIAL SOLD TO VISAYAN
STEVEDORING-TRANSPORTATION CO. - MILD
STEEL PLATES, 60" x 1/4" x 20 ft.
ON OUR SHOP'S ORDER T-7433, DATED
MARCH 20, 1939

ROBERT W. HUNT COMPANY, ENGINEERS
Report of Inspections and Tests, 7-29-38

Our File 7850
Our Order SM-36354

Inspector's Report No.74 Sheet No.4

Made by Bethlehem Steel Export Corporation
For Atlantic, Gulf & Pacific Co. Client's Order 6167

Date Inspected	7-29-38
Shipper's Weight	1540
Heat Number	60J402
Dimensions of Test Piece	1.590 x .258
Yield Point in lbs. per sq. in.	37300
Tensile Strength in lbs. per sq. in.	61400 27.4 tons/in ²
% Elongation in In.	29.0
% Reduction of Area	62.9
Bends - Cold 180 degrees	O.K.
Manufacturer's Chemical Analysis:-	
Car.	.12
Mang.	.54
Phos.	.011
Sul.	.023

(Sgd.) ROBERT W. NEIMHOLE
(Engineer of Test)

a true copy
ATLANTIC, GULF & PACIFIC COMPANY
OF MANILA

per

E. L. Reynolds
E. L. REYNOLDS

Read test 180°
Signature
Signature
© 2021
REGISTER OF SHIPPING
B. NELSON
MANILA