

COPY OF CERTIFICATE OF
INSPECTION AND TEST OF MATERIALS SOLD TO VISAYAN
STEVEDORE-TRANSPORTATION CO. - M. S. PLATES.
48" X 1/4" AND 60" X 1/4" ON OUR SHOPS
ORDER T-6999, DATED FEBRUARY 27, 1939

ROBERT W. HUNT COMPANY, ENGINEERS
Report of Inspections and Tests, 7-29-38

Our File 7850

Our Order SM-36354

Inspector's Report No. 74 Sheet No. 4

Made by Bethlehem Steel Export Corporation

For Atlantic, Gulf & Pacific Co. Client's Order 6167

	<u>60"x1/4"x360"</u>	<u>48"x1/4"x360"</u>
Date Inspected	7-29-38	7-29-38
Shipper's Weight	1540	1270
Heat Number	60J402	66J381
Dimensions of Test Piece	1.590 x .258	1.710 x .190
Yield Point in lbs. per sq. in.	37300	41800
Tensile Strength in lbs. per sq. in.	61400	68800
% Elongation in in.	29.0	26.0
% Reduction of Area	62.9	58.5
Bends - Cold 180°	O.K.	O.K.
Manufacturer's Chemical Analysis:-		
Car.	.12	.12
Mang.	.54	.51
Phos.	.011	.013
Sul.	.023	.022

(Sgd.) ROBERT W. NEIMHOLE
(Engineer of Test)

a true copy
ATLANTIC, GULF & PACIFIC COMPANY
OF MANILA

per

E. L. Reynolds
E. L. REYNOLDS



© 2021

Lloyd's Register
Foundation

W103-0027