

COPY OF CERTIFICATE OF
INSPECTION AND TEST OF MATERIALS SOLD TO VISAYAN
STEVEDORE-TRANSPORTATION CO. - STEEL ANGLES,
3-1/2" X 3" X 5/16" X 30 FT. AND 4" X 3"
X 5/16" X 30 FT. ON OUR SHOPS ORDER
T-7200, DATED MARCH 6, 1939

ROBERT W. HUNT COMPANY, ENGINEERS
Report of Inspections and Tests, 8-23-38

Our File 7850
Our Order SM-36355

Inspector's Report #14237 & #14243

Made by Carnegie-Illinois Steel Corp. Client's Order #6181
For Atlantic, Gulf & Pacific Co.

| | <u>3-1/2" X 3" X 5/16"</u> | <u>4" X 3" X 5/16"</u> |
|--------------------------------------|----------------------------|------------------------|
| Date Inspected | 8-23-38 | 8-23-38 |
| Shipper's Weight | 9960 | |
| Heat Number | 313155 | 306151 |
| Dimensions of test piece Area Sq.In. | .4758 | .5022 |
| Yield Point in lbs. per sq. in. | 38880 | 38630 |
| Tensile Strength in lbs. per sq. in. | 63680 | 65320 |
| %Elongation in inch | 26.2 | 27.5 |
| % Reduction of Area | 54.6 | 50.1 |
| Bends - Cold 180° | O.K. | O.K. |
| Manufacturer's Chemical Analysis:- | | |
| Car. | .21 | .22 |
| Mang. | .48 | .61 |
| Phos. | .016 | .017 |
| Sul. | .034 | .031 |

(Sgd.) ROBERT W. NEIMHOLE
(Engineer of Test)

a true copy
ATLANTIC, GULF & PACIFIC COMPANY
OF MANILA

per

E. L. Reynolds
E. L. REYNOLDS



© 2021

Lloyd's Register
Foundation

W103-0028