

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

ENCLOSURE

14th February, 1935.

Dear Sir,

I am in receipt of your letter of the 9th instant respecting the m.v. "TIXIER" ex "LITTLE EVY", and have to acquaint you that with 4 SCSA oil engines for main propelling purposes, having 6 cylinders 310 mm. diameter by 450 mm. stroke, revolutions per minute 310, maximum pressure in cylinders 45 kg. per sq. cm., M.I.P. 6.9 kg. per sq. cm., B.H.P. 400,  $GD^2$  of fly-wheel 1450 kg.M<sup>2</sup>, diameter of propeller 2000 mm. and screwshaft with continuous liner, the proposed sizes of shafting, viz:- thrust shaft 140 mm. intermediate shaft 140 mm. and screwshaft 164 mm. diameter, will be approved.

One copy of the plan, forwarded by you, is returned herewith.

I am, Dear Sir,

Yours faithfully,

Secretary.

The Surveyors,

ROTTERDAM.



© 2020

Lloyd's Register  
Foundation

state in which tanks oil fuel will be carried.

12-3-35 &  
✓ 13-3-35