

OCT 23 1937

Index No.

Lloyd's Register of Shipping. Feb 1992

Ship's Name SS. "LANCASTER CITY" ex "PENRHYN" Official No. 101755.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in Bangor 19/9/32.

Alterations now carried out:-

After crewspace below R.Q. deck now converted for use as storeroom. New hatchway fitted opening to this space on starboard side R.Q. deck aft, abreast crewspace deck house abaft LR casing. New hatchway $17\frac{1}{2} \times 17\frac{1}{2}$ " Coaming 18" high $\frac{1}{4}$ " steel plate closed by W.T. bolted steel cover.

W.C. in after crewspace deckhouse now removed to stow on starboard side right aft alongside original W.C., new sanitary discharge fitted about 24' below R.Q. deck, no storm valve. (Note: there are now two sanitary discharges through counter aft)

Two new cowl ventilators now fitted on forecastle deck to crewspace. boamings 6" diam. 2'-6" high $\times \frac{1}{4}$ " instead of one 6" diam. 15" \times 2" (now removed). closed by wooden plugs & canvas covers.

Two 4" diam. goosenecks on Bridge Deck to accommodation removed and replaced by two 6" mushroom ventilators with screw down tops.

John Lewis

Steelwood,

21st Oct 1937.

Noted *Part B*

W1031-0298.1

28 OCT 1937