

5m.5.32.

## FREEBOARD REPORT on the

Penrhyn.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:-

- ① One tarpaulin being provided for the bunker hatchway on Casing Top.
- ② Efficient means of closing being provided for all ventilator coamings and airpipes, and ventilator coamings being repaired or renewed where necessary to Surveyor's satisfaction.
- ③ Suitable provision being made for rigging lifelines which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.
- ④ The freeing port area in the Raised Quarter Deck Bulwark being increased to 12 sq. feet and in the freeboard deck bulwark to 12 sq. feet, on each side of ship in each case.
- ⑤ Means of securing doors closing openings in Forecastle Bulkhead being made efficient to Surveyor's satisfaction.

Asst. Dir.  
Dunrobin  
29.9.32

Convention



© 2020  
81

Lloyd's Register  
Foundation  
28.9.32  
103-0310

1 - 0 1/2  
0 - 11