

In forwarding the enclosed report on Survey for
Convention Freeboard for the steamer "SOUND FISHER". we have

W1032-0127

C. 7c, 11.28.

FREEBOARD REPORT on the

Sound Fisher.

It is submitted the Freeboards given on the accompanying
form, being those required by the Tables, merit approval, subject to:-

- ① Additional cleats being fitted to Nos 1. + 2. Cargo Hatchway coamings so that
spacing of cleats does not exceed 24 inches.
- ② Permanent chain attachments being fitted to Fresh Bunker Scuttles on
Raised Quarter Deck.
- ③ Ventilator coamings 48 and 51 inches in height being efficiently stayed and
satisfactory means of closing being provided for all ventilator coamings not
already supplied with same.
- ④ Airpipes on Raised Quarter Deck being increased in height to 30 inches,
and satisfactory means of closing being provided for all airpipes.
- ⑤ A gangway, lifelines or other efficient means being provided in the
well for the protection of the crew.
- ⑥ Freeing Port Area in Raised Quarter Deck bulwarks being increased to
16½ square feet on each side of ship.

The Convention Freeboards being less favourable than the existing freeboards, the latter have been re-assigned.
Agst the. Owners' Convention.
Bms. 31/5/32

J. M. M.

R. H. K.

518.

30.5.32

4-84 6

4-64 4