

'GRANNY SUZANNE' (ex 'Springwave')

IT IS SUBMITTED the Barry Surveyors be informed that, to permit of the Figure '1' being assigned, the equipment of this vessel should be in accordance with or equivalent to the requirements of letter 'g', Table 53 of the Rules, which requires 3 bower anchors to be supplied and the cable to be of 165 fathoms 1.1/16" diameter.

To comply with the above, it will therefore be necessary to supply an additional bower anchor, tested as per Rules, but may be of 9 cwts. stockless.

So far as the cable is concerned, the 130 fathoms of 15/16 diameter and below, being of the renewable diameter, cannot be accepted, and to comply with the requirements of the Rules an additional 30 fathoms of 1.1/16 cable should be supplied.

The wires stated to be on board could be accepted but an additional stream wire of 60 fathoms and 2½ inches circumference should be placed on board.

Ltr. 3-12-47

28-11-47

Ansd. 5-12-47

3 plans

sh. *AD*

5.12.47.

[Handwritten signature]



© 2020

Lloyd's Register
Foundation

W1032-0232