

1m.10.40.

Shipbuilding Corporation Ltd. (Wear Branch), Sunderland.

Yard No. 7.

Similar to the "EMPIRE MAURITIUS" etc.

F.E.
(FBD.)

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s. "EMPIRE MOMBASA" Rpt. Sld. No. 34401

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

D to W dk 38' (flat sheer). D to 2nd dk 27.25' (flat sheer). D for scantlings
 1st Long. No. 15725 Depth "d" 21.83 37'.
 2nd Long. No. 39525 Proportions = $\frac{L}{D}$ 11.18
 Framing As approved Sheerstrake As approved

The scantlings of this "C" Type Standard Ship have been approved for a draught of 30" in excess of that corresponding to the freeboard which could be assigned, as a C.S.S. vessel having a tonnage opening.

The tank top plating has been increased in thickness under the hatchways in lieu of ceiling.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to

be classed ~~as~~ "With freeboard"
 1.46 Sld

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

2 Dks "Longitudinal framing at decks" "Part elec. welded"
 Cell DB 317' 1292 tons, tank in way of tunnel 323t, wing tanks in
 mchy space 323t, fwd 280t, FPT 187t, APT 160t
 FK, 7 BH, Cem., Lloyd's A & CP

F 38'
 O.L. 447.8'
 E.S.D.

at

The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed.

Insert in S.R.L.:- (A power anchor and 45 fathoms of chain cable to be supplied).

W1038-0009

DOUBLE BOTTOM.

Solid Floors, thickness and spacing

42 EVERY FRAME

Bridge Deck, Angle. F or F