

W1044-0099

TELEGRAMS: "PROVING, CARDIFF."
TELEPHONE, POST OFFICE NO 482.

LICENSED BY THE BOARD OF TRADE.

GEO. W. PENN, C.E.
SUPERINTENDENT.

GOODS CONSIGNED
BY WATER TO GLAMORGANSHIRE CANAL
BY RAIL VIA RIVERSIDE BRANCH, GREAT WESTERN RAIL.

LLOYD'S REGISTER,
LONDON.

*Lloyd's Proving House,
Dumball's Road,*

Cardiff. 4th Oct 1920 192

In reply please quote:-

REC 5 OCT 1920
ANS 6

PMC.

Dear Sir,

I beg to acknowledge receipt of your letter dated the
1st instant, and as requested have pleasure in furnishing the following
particulars.

Cardiff Certificate of Test No 20008.
Date of Certificate. 13th December 1917.
Description. 270 fathoms of 2.3/16" Stud link Cable. 16 joining and
4 end shackles, 2 joining and 2 end shackles spare.

Weight of Cable and 16 & 4 shackles. Cwts 647-3- 7
" " 2 and 2 spare shackles 4-1-21

Breaking strain. 120.5 Tons
Tensile strain. 86½ "

Size of links. Length 13½"
Breadth 7.11/16"

Makers. Messrs Brown Lenox and Co Ltd Pontypridd.

Cardiff Certificate of Test No 12460 Drop Test Certificate No 2841.

Date of Certificate 11 Sept 1917

Description. Lenox Wedge Stockless Anchor.

Test. 50.5 tons

Length of shank 7 feet 8 inches
" " arm. 4 feet 6 inches

Diameter of trend 10½" x 7.5/16"

Weight. 64-0-0

Weight of head and pin Cwts 44-1-14

" " shank & shackle 19-2-14

Makers. Messrs Brown Lenox and Co Ltd Pontypridd.

I am, Dear Sir

Yours faithfully,

F.H. Mayne. Esq
Assistant to the Secretary
Lloyds Register of Shipping LONDON.

4.76
57
1571
© 2020

Lloyd's Register
Foundation

Referred to the ~~Ind~~ Ship Surveyor.

P. Mc

78 No

5 OCT 1920

It is submitted copy of this letter
be forwarded to the Trieste office for
the compilation of the 1st Entry report
on this vessel

BH
5/10/20.



© 2020

Lloyd's Register
Foundation